



**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION**

**APPLICATION FOR OSHPD SPECIAL SEISMIC
CERTIFICATION PREAPPROVAL (OSP)**

OFFICE USE ONLY

APPLICATION #: **OSP – 0048 – 10**

OSHPD Special Seismic Certification Preapproval (OSP)

Type: New Renewal

Manufacturer Information

Manufacturer: CLIMACOOOL Corp.

Manufacturer's Technical Representative: Gus Olivera

Mailing Address: 15 S. Virginia Avenue, Oklahoma City, OK 73106

Telephone: (405) 815-3011 Email: golivera@climacoolcorp.com

Product Information

Product Name: The Ultimate (UCW/H) Series Water Cooled Modular Chiller and CoolLogic Master Control Panel

Product Type: Water Cooled Modular Chiller and Master Control Panel

Product Model Number: UCW/H030, UCW/H050, UCW/H070, and CoolLogic Master Control Panel
(List all unique product identification numbers and/or part numbers)

General Description: Modular Chillers and Master Control Panel. Seismic enhancements made to the test units shall be incorporated into the production units.

Mounting Description: Chillers: rigid base mounted and vibration spring isolated.
Master Control Panel: rigid wall mounted.

Applicant Information

Applicant Company Name: CLIMACOOOL Corp.

Contact Person: Gus Olivera

Mailing Address: 15 S. Virginia Avenue, Oklahoma City, OK 73106

Telephone: (405) 815 0311 Email: golivera@climacoolcorp.com

I hereby agree to reimburse the Office of Statewide Health Planning and Development review fees in accordance with the California Administrative Code, 2013.

Signature of Applicant:  Date: 3/16/2015

Title: Director of Engineering Company Name: CLIMACOOOL Corp.

"Access to Safe, Quality Healthcare Environments that Meet California's Diverse and Dynamic Needs"





**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION**

California Licensed Structural Engineer Responsible for the Engineering and Test Report(s)

Company Name: Buehler & Buehler Structural Engineers, Inc

Name: Scott Hooker California License Number: S3937

Mailing Address: 600 Q St. Suite 200, Sacramento, CA 95811

Telephone: (916) 443 0303 Email: shooker@bbse.com

Supports and Attachments Preapproval

- Supports and attachments are preapproved under OPM- _____
(Separate application for OSHPD Preapproval of Manufacturer's Certification (OPM) of Supports and attachments is required)
- Supports and attachments are not preapproved

Certification Method

- Testing in accordance with: ICC-ES AC156
- Other (Please Specify): _____


Testing Laboratory

Company Name: Curtiss Wright Flow Control Company - TRENTEC

Contact Name: Marie S. Nemier

Mailing Address: 4600 East Tech Drive, Cincinnati, OH 45245

Telephone: (513) 528 7900 Email: mnemier@curtisswright.com





**OFFICE OF STATEWIDE HEALTH PLANNING AND DEVELOPMENT
FACILITIES DEVELOPMENT DIVISION**

Seismic Parameters

Design in accordance with ASCE 7-10 Chapter 13: Yes No

Design Basis of Equipment or Components (F_p/W_p) = 1.39 / 4.34 (Chiller – Rigid / Isolated), 1.45 (Control Box)

S_{DS} (Design spectral response acceleration at short period, g) = 1.93

a_p (In-structure equipment or component amplification factor) : 1.0 / 2.5 (Chiller - Rigid / Isolated), 2.5 (Control Box)

R_p (Equipment or component response modification factor) 2.5 / 2.0 (Chiller – Rigid / Isolated), 6.0 (Control Box)

Ω_0 (System overstrength factor) = 2.0

I_p (Importance factor) = 1.5

z/h (Height factor ratio) = 1.0

Equipment or Component Natural Frequencies (Hz) See Table 3

Overall dimensions and weight (or range thereof) = See Table 1

Equipment or Components @ grade designed in accordance with ASCE 7-10 Chapter 15 Yes No

Design Basis of Equipment or Components (V/W) = _____

S_{DS} (Design spectral response acceleration at short period, g) = _____

S_{D1} (Design spectral response acceleration at 1 second period, g) _____

R (Response modification coefficient) = _____

Ω_0 (System overstrength factor) = _____

C_d (Deflection amplification factor) = _____

I_p (Importance factor) = 1.5

Height to Center of Gravity above base = _____

Equipment or Component Natural Frequencies (Hz) = _____

Overall dimensions and weight (or range thereof) = _____

Tank(s) designed in accordance with ASME BPVC, 2010 Yes No

List of Attachments Supporting Special Seismic Certification

Test Report(s) Drawings Calculations Manufacturer's Catalog

Other(s) (Please Specify): Operability Test Letters

OSHPD Approval (For Office Use Only) – Approval Expires on December 31, 2019


Signature:  Date: 9/15/2016

Print Name: M. R. Karim Title: SHFR

Special Seismic Certification Valid Up to : S_{DS} (g) = 1.93 z/h = 1.0

Condition of Approval (if applicable): **Chiller with seismic bracket per attachment # 2 can be installed with or without vibration isolators (excludes all non-factory installed accessories). ClimaCool UC*COOLLOGIC Control Panel**

(Model: S10S0261N01) is approved for wall mounted configuration only.





Special Seismic Certification
OSHDP Preapproval



ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel

Table 1. Certified Product List

UCW/H Water Cooled Modular Chiller

<i>Model Number</i> ²	<i>Nominal Capacity</i>	<i>Tested/ Interpolated</i>	<i>Length (in)</i>	<i>Width (in)</i>	<i>Height (in)</i>	<i>Operating Weight¹ (lbs)</i>
UCW/H030	208/230/460/575/3/60	UUT-1	55 1/2	34 1/4	65 1/8	1,480
UCW/H050	208/230/460/575/3/60	Interpolated	55 1/2	34 1/4	65 1/8	2,200
UCW/H070	208/230/460/575/3/60	UUT-2	55 1/2	34 1/4	65 1/8	2,450

1. Operating weight includes refrigerant charge, compressor oil, and water.
2. Certified units include seismic bracket kit shown in Attachment #2

CoreLogic Master Control Panel

<i>Model Number</i>	<i>Nominal Capacity</i>	<i>Tested/ Interpolated</i>	<i>Length (in)</i>	<i>Width (in)</i>	<i>Height (in)</i>	<i>Operating Weight (lbs)</i>
S10S0261N01	N/A	UUT-3	7 3/4	24 1/2	24 1/4	50



Special Seismic Certification
OSHPD Preapproval



ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel

Table 2. Certified Sub-Component List

Compressor					
<i>Part Number</i>	<i>Nominal capacity</i>	<i>Voltage</i>	<i>Manufacturer</i>	<i>Material</i>	<i>Interpolated / Included With Test</i>
ZP182KCE	15 Tons	208/230-460-575	Copeland	Carbon Steel/Copper	UUT-1
ZP295KCE	25 Tons	208/230-460-575	Copeland	Carbon Steel/Copper	Interpolated
ZP385KCE	35 Tons	208/230-460-575	Copeland	Carbon Steel/Copper	UUT-2

Condenser Braze Plate Heat Exchanger			
<i>Part Number</i>	<i>Manufacturer</i>	<i>Material</i>	<i>Interpolated / Included With Test</i>
ACH-230DQ-166H	AlfaLaval	Stainless Steel 316/Copper	UUT-1
ACH-500DQ-142H	AlfaLaval	Stainless Steel 316/Copper	Interpolated
ACH-500DQ-166H	AlfaLaval	Stainless Steel 316/Copper	UUT-2

Evaporator Braze Plate Heat Exchanger			
<i>Part Number</i>	<i>Manufacturer</i>	<i>Material</i>	<i>Interpolated / Included With Test</i>
ACH-230DQ-142H	AlfaLaval	Stainless Steel 316/Copper	UUT-1
ACH-500DQ-118H	AlfaLaval	Stainless Steel 316/Copper	Interpolated
ACH-500DQ-142H	AlfaLaval	Stainless Steel 316/Copper	UUT-2

Control Box Assembly			
<i>Part Number</i>	<i>Manufacturer</i>	<i>Material</i>	<i>Interpolated / Included With Test</i>
S10S0261N01	ClimaCool	Galvanized Steel and others	UUT-3



**Special Seismic Certification
OSHPD Preapproval**



***ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel***

Table 3. UUT Summary

Model Number	Nominal Capacity	UUT Mark	Mounting	Excitation Direction	Frequency* (Hz)	Length (in)	Width (in)	Height (in)	Operating Weight (lbs)
UCW/H030	30 ton	UUT-1	Rigid Base Mount	X	11.1	55 1/2	34 1/4	65 1/8	1,480
				Y	13.1				
				Z	22.0				
			With Spring Isolators	X	1.9				
				Y	2.3				
				Z	7.6				
UCW/H070	70 ton	UUT-2	Rigid Base Mount	X	9.2	55 1/2	34 1/4	65 1/8	2,450
				Y	7.2				
				Z	22.8				
			With Spring Isolators	X	2.2				
				Y	1.3				
				Z	7.0				
Control Panel (S10S0261N01)	N/A	UUT-3	Wall Mounted	X	N/A	7 3/4	24 1/2	24 1/4	50
				Y	N/A				
				Z	N/A				

* Frequencies are for units prior to ICC ES AC-156 testing.



**Special Seismic Certification
OSHPD Preapproval**



***ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel***

Table 4. UUT Summary Sub-Component List

UUT-1 UCW/H030				
Sub-Component	Description	Part Number	Manufacturer	Material
Header Tube Assembly	Header Tube Assembly	C28B0001N01	SHARP IRON LLC	Schedule 40 Steel
Cabinet Assembly	Cabinet Assembly	83P0201N02	CLIMATE MASTER	Galvanized Steel
Seismic Kit Assembly	Seismic Kit Assembly	83K0119N01	CLIMATE MASTER	Galvanized Steel
Condenser Braze Plate Heat Exchanger	Condenser Braze Plate Heat Exchanger	ACH-230DQ-166H	AlfaLaval	Stainless Steel 316/Copper
Evaporator Braze Plate Heat Exchanger	Evaporator Braze Plate Heat Exchanger	ACH-230DQ-142H	AlfaLaval	Stainless Steel 316/Copper
Compressor	15 Ton Compressor	ZP182KCE	Copeland	Steel/Copper

UUT-2 UCW/H070				
Sub-Component	Description	Part Number	Manufacturer	Material
Header Tube Assembly	Header Tube Assembly	C28B0001N01	SHARP IRON LLC	Schedule 40 Steel
Cabinet Assembly	Cabinet Assembly	83P0201N01	CLIMATE MASTER	Galvanized Steel
Seismic Kit Assembly	Seismic Kit Assembly	83K0119N01	CLIMATE MASTER	Galvanized Steel
Condenser Braze Plate Heat Exchanger	Condenser Braze Plate Heat Exchanger	ACH-500DQ-166H	AlfaLaval	Stainless Steel 316/Copper
Evaporator Braze Plate Heat Exchanger	Evaporator Braze Plate Heat Exchanger	ACH-500DQ-142H	AlfaLaval	Stainless Steel 316/Copper
Compressor	35 Ton Compressor	ZP385KCE	Copeland	Steel/Copper

UUT-3 Control Box Assembly				
Sub-Component	Description	Part Number	Manufacturer	Material
S10S0261N01	Control Box Assembly	S10S0261N01	ClimaCool	Galvanized Steel and others

***ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel***

Shake Table Test Setup Test #2

UUT Designation	UUT 3	Seismic Parameters							
Identification No.	Q0005-03-01-01	Building Code	Test Criteria	S_{Ds} (g)	z/h	Horizontal		Vertical	
Model No:	S10S0261N01					A_{FLX-H}	A_{RIG-H}	A_{FLX-V}	A_{RIG-V}
Attachment Method	Wall Mounted w/ (8) 1/4" bolts	CBC 2013	AC 156	1.93	1.0	3.09g	2.32g	1.29g	0.51g



Overall View of Test Item #Q0005-03-01-01 ClimaCool UC* COOLLOGIC Control Panel, Model: S10S0261N01



Alternate View of Test Item #Q005-03-01-01

Notes: The UUTs were full of contents during the test.
 After the test, the UUT was functional and the structural integrity of the component attachment and force-resisting systems was maintained.

ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel

Shake Table Test Setup Test #5

UUT Designation	UUT 1	Seismic Parameters							
Identification No.	Q0005-01-01-01	Building Code	Test Criteria	S_{Ds} (g)	z/h	Horizontal		Vertical	
Model No:	UCW030AHASACM0S					A_{FLX-H}	A_{RIG-H}	A_{FLX-V}	A_{RIG-V}
Attachment Method	Unit mounted to C6x13 frame with (6) 5/8" diameter grade 8 bolts with 1 1/2" diameter oversized washers and beveled flat washers. C6 frame mounted to the table with (10) 1/2" diameter grade 8 bolts.	CBC 2013	AC 156	1.93	1.0	3.09g	2.32g	1.29g	0.51g



Overall View of Test Item #Q0005-01-01-01 ClimaCool Wtr 30-ton Chiller with UCH/W Header Bank End Cap Kit Model: UCW030AHASACM0S with UC*GC001 mounted on the C-Channel Base

Notes: The UUTs were full of contents during the test.
 After the test, the UUT was functional and the structural integrity of the component attachment and force-resisting systems was maintained.


*ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel*

Shake Table Test Setup Test #6

UUT Designation	UUT 1	Seismic Parameters							
Identification No.	Q0005-01-01-01	Building Code	Test Criteria	S_{Ds} (g)	z/h	Horizontal		Vertical	
Model No:	UCW030AHASACM0S					A_{FLX-H}	A_{RIG-H}	A_{FLX-V}	A_{RIG-V}
Attachment Method	Unit mounted to C6x13 frame with (6) 5/8" diameter grade 8 bolts with 1 1/2" diameter oversized washers and beveled flat washers. C6 frame is welded with (2) 4" lengths of 5/16" fillet weld to (4) Mason Spring Isolators (SLRS0-4).	CBC 2013	AC 156	1.93	1.0	3.09g	2.32g	1.29g	0.51g



Overall View of Test Item #Q0005-01-01-01 ClimaCool Wtr 30-ton Chiller with UCH/W Header Bank End Cap Kit Model: UCW030AHASACM0S with UC*GC001 mounted on the C-Channel Base with Isolators




Close Up View of the Mason Industries Vibration Isolators P/N: SLRS0-4-C2-500

Notes: The UUTs were full of contents during the test.
 After the test, the UUT was functional and the structural integrity of the component attachment and force-resisting systems was maintained.


*ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel*

Shake Table Test Setup Test #7

UUT Designation	UUT 2	Seismic Parameters							
Identification No.	Q0005-02-01-01	Building Code	Test Criteria	S_{Ds} (g)	z/h	Horizontal		Vertical	
Model No:	UCW070AFASACM0S					A_{FLX-H}	A_{RIG-H}	A_{FLX-V}	A_{RIG-V}
Attachment Method	Unit mounted to C6x13 frame with (6) 5/8" diameter grade 8 bolts with 1 1/2" diameter oversized washers and beveled flat washers. C6 frame mounted to the table with (10) 1/2" diameter grade 8 bolts.	CBC 2013	AC 156	1.93	1.0	3.09g	2.32g	1.29g	0.51g



Overall View of Test Item #Q0005-02-01-01 ClimaCool Wtr 70-ton Chiller with UCH/W Header Bank End Cap Kit Model: UCW070AfASACM0S with UC*GC001 mounted on the C-Channel Base




Alternate View of Test Item #Q0005-02-01-01

Notes: The UUTs were full of contents during the test.
 After the test, the UUT was functional and the structural integrity of the component attachment and force-resisting systems was maintained.


*ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel*

Shake Table Test Setup Test #8

UUT Designation	UUT 2	Seismic Parameters							
Identification No.	Q0005-02-01-01	Building Code	Test Criteria	S_{Ds} (g)	z/h	Horizontal		Vertical	
Model No:	UCW070AFASACM0S					A_{FLX-H}	A_{RIG-H}	A_{FLX-V}	A_{RIG-V}
Attachment Method	Unit mounted to C6x13 frame with (6) 5/8" diameter grade 8 bolts with 1 1/2" diameter oversized washers and beveled flat washers. C6 frame is welded with (2) 4" lengths of 5/16" fillet weld to (4) Mason Spring Isolators (SLRS0-4).	CBC 2013	AC 156	1.93	1.0	3.09g	2.32g	1.29g	0.51g



Overall View of Test Item #Q0005-02-01-01 ClimaCool Wtr 70-ton Chiller with UCH/W Header Bank End Cap Kit Model: UCW070AFASACM0S with UC*GC001 mounted on the C-Channel Base with Isolators



Close Up View of the Mason Industries Vibration Isolators P/N: SLRS0-4-C2-840

Notes: The UUTs were full of contents during the test.
 After the test, the UUT was functional and the structural integrity of the component attachment and force-resisting systems was maintained.

ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel

Rigid Base Mount with C6 base frame



Spring Isolated with C6 base frame

BUEHLER & BUEHLER
STRUCTURAL ENGINEERS, INC.

JOB CLIMACOOL Special Seismic Certification
 JOB NO. S10-00500 DATE 1/29/2010
 CLIENT ClimaCool BY ALI SHEET NO. 3

BUEHLER & BUEHLER
STRUCTURAL ENGINEERS, INC.

JOB CLIMACOOL Special Seismic Certif.
 JOB NO. S10-00500 DATE 1/29/2010
 CLIENT ClimaCool BY ALI SHEET NO. 4






Special Seismic Certification
OSHPD Preapproval



ClimaCool UCW/H Series Water Cooled Modular Chillers
CoolLogic Master Control Panel

Model Number Nomenclature


Ultimate Chiller Solution Model Key



FOR REFERENCE ONLY


Attachment #2 Seismic Bracket Kit

47F1549GNP
TOP BRACKET




REAR VIEW


47F1546GNP
REAR BRACKET



TOP VIEW




ISO VIEW




LEFT SIDE VIEW

47F1547GNP
LEFT BRACKET



FRONT VIEW

47F1545GNP
FRONT BRACKET



RIGHT SIDE VIEW

47F1548GNP
RIGHT BRACKET

CLIMACOOL™
THE ULTIMATE CHILLER SOLUTION®

This document is the sole property of ClimaCool Corp. Distribution of this document is forbidden without the written consent of ClimaCool Corp. Design changes to any portion of this document may occur without notice.

CHILLER LAYOUT: UCW/H030, 050, 070


CC P/N: 83K119N01

PROJECT: UNIT SEISMIC BRACKET KIT UC*


SIZE	FSCM NO.	DWG NO.
B		CCE-83K0119N01 UNIT SEISMIC BRACKET KIT UC*

SCALE	None	DATE	3/05/2010	SHEET	1 OF 1	REV.	Orig.
-------	------	------	-----------	-------	--------	------	-------


Attachment #2 Seismic Bracket Kit




TOP



LEFT



FRONT



RIGHT


					UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES. TOLERANCES AS FOLLOWS: DECIMALS - ± .031 ANGLES - ± 1°				15 S. Virginia Avenue Oklahoma City, Ok 73106 Ph: 405-815-3000 Fax: 405-815-3052			
							TITLE: 85 TON SHC HEAT RECOVERY CHILLER					
- INITIAL RELEASE					-	-	Nov-20-15	VIEW_REFERENCES				
REV	DESCRIPTION				BY	PCN	DATE	ENG	Pro/E	DRAWING NO:	SCALE: 0.025	REV
									A	DRAWN BY: T. SMOCK ENGINEER: T. SMOCK	Nov-20-15 Nov-20-15	A
									SHEET: 1 OF 1			

Material Properties	
Grade	1005-1026
Shape	Square Tube
Wall Thickness	0.120" ± 0.012"
Straightness Tolerance	1/16" per 3'
Yield Strength	32,000 psi
Specification Met	ASTM A513
Construction	Hot Rolled
Material Composition	-
Carbon	0.13-0.20%
Manganese	0.30-0.90%
Silicon	0.15-0.30%
Phosphorous	0.04% Max
Sulfur	0.50% Max
Iron	98.06-99.42%
Nominal Density	0.283 lb/cu. in.
Thermal Coefficient of Expansion per °F	6.7-7.5e-6
Elongation Range	10-36%

Attachment #2 Seismic Bracket Kit

TAB_FRONT_LEFT_BOT Welded to BOT_LEFT_ANGLED_SQUARE_TUBE

Fastened to FRONT_LEFT_VERT_SQUARE_TUBE
w/ 3/8" Bolt



71.306

1.500

TAB_REAR_LEFT_MID Welded to BOT_LEFT_ANGLED_SQUARE_TUBE

Fastened to MID_HORZNTL_LEFT_SQUARE_TUBE
w/ 5/16" Bolt

Fastened to REAR_LEFT_VERT_SQUARE_TUBE
w/ 3/8" Bolt

REV	DESCRIPTION	BY	PCN	DATE	ENG
-	INITIAL RELEASE	-	-	Nov-20-15	-

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.
TOLERANCES AS FOLLOWS:
DECIMALS - ± .031
ANGLES - ± 1°



15 S. Virginia Avenue
Oklahoma City, Ok 73106
Ph: 405-815-3000
Fax: 405-815-3052

TITLE: STEEL, SQUARE TUBE

FINISH: ROUGH	Pro/E	DRAWING NO:	BOT_LEFT_ANGLED_TUBE_TABS
MATERIAL: LOW-CARBON STEEL	SIZE A	DRAWN BY: T. SMOCK	Nov-20-15
		ENGINEER: T. SMOCK	Nov-20-15
		SCALE: 0.075	REV A
		SHEET: 1 OF 1	

Material Properties	
Grade	1005-1026
Shape	Square Tube
Wall Thickness	0.120" ± 0.012"
Straightness Tolerance	1/16" per 3'
Yield Strength	32,000 psi
Specification Met	ASTM A513
Construction	Hot Rolled
Material Composition	-
Carbon	0.13-0.20%
Manganese	0.30-0.90%
Silicon	0.15-0.30%
Phosphorous	0.04% Max
Sulfur	0.50% Max
Iron	98.06-99.42%
Nominal Density	0.283 lb/cu. in.
Thermal Coefficient of Expansion per °F	6.7-7.5e-6
Elongation Range	10-36%

Attachment #2 Seismic Bracket Kit



Fastened to MID_HORZNTL_RIGHT_SQUARE_TUBE
w/ 5/16" Bolt

Fastened to FRONT_RIGHT_VERT_SQUARE_TUBE
w/ 3/8" Bolt

TAB_FRONT_RIGHT_MID Welded to
BOT_RIGHT_ANGLED_SQUARE_TUBE

TAB_REAR_RIGHT_BOT Welded to
BOT_RIGHT_ANGLED_SQUARE_TUBE

Fastened to REAR_RIGHT_VERT_SQUARE_TUBE
w/ 3/8" Bolt

1.500

71.306

1.500



REV	DESCRIPTION	BY	PCN	DATE	ENG
-	INITIAL RELEASE	-	-	Nov-20-15	-

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.
TOLERANCES AS FOLLOWS:
DECIMALS - ± .031
ANGLES - ± 1°



15 S. Virginia Avenue
Oklahoma City, Ok 73106
Ph: 405-815-3000
Fax: 405-815-3052

TITLE: **STEEL, SQUARE TUBE**

FINISH: ROUGH	Pro/E	DRAWING NO:	BOT_RIGHT_ANGLED_TUBE_TABS
MATERIAL: LOW-CARBON STEEL	SIZE A	DRAWN BY: T. SMOCK	Nov-20-15
		ENGINEER: T. SMOCK	Nov-20-15
		SCALE: 0.075	REV A
		SHEET: 1 OF 1	

Material Properties	
Grade	1005-1026
Shape	Square Tube
Wall Thickness	0.120" ± 0.012"
Straightness Tolerance	1/16" per 3'
Yield Strength	32,000 psi
Specification Met	ASTM A513
Construction	Hot Rolled
Material Composition	-
Carbon	0.13-0.20%
Manganese	0.30-0.90%
Silicon	0.15-0.30%
Phosphorous	0.04% Max
Sulfur	0.50% Max
Iron	98.06-99.42%
Nominal Density	0.283 lb/cu. in.
Thermal Coefficient of Expansion per ° F	6.7-7.5e-6
Elongation Range	10-36%

Attachment #2 Seismic Bracket Kit


FRONT_ANGLED_TAB_BOT Welded to FRONT_ANGLED_SQUARE_TUBE

FRONT_ANGLED_TAB_TOP-2 Welded to FRONT_ANGLED_TAB_TOP-1 and FRONT_ANGLED_SQUARE_TUBE

FRONT_ANGLED_TAB_TOP-1 Welded to FRONT_ANGLED_SQUARE_TUBE and FRONT_ANGLED_TAB_TOP-2

Fastened to FRONT_RIGHT_VERT_SQUARE_TUBE w/ 3/8" Bolt

Fastened to Corner Post w/ 3/8" Bolt



REV	DESCRIPTION	BY	PCN	DATE	ENG
-	INITIAL RELEASE	-	-	Nov-20-15	-

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.
TOLERANCES AS FOLLOWS:
DECIMALS - ± .031
ANGLES - ± 1°

CLIMA COOL
ULTIMATE CLIMATE SOLUTIONS

15 S. Virginia Avenue
Oklahoma City, Ok 73106
Ph: 405-815-3000
Fax: 405-815-3052

TITLE: **STEEL, SQUARE TUBE**

FINISH: ROUGH	Pro/E	DRAWING NO: FRONT_ANGLED_WELDED_TABS
MATERIAL: LOW-CARBON STEEL	SIZE A	DRAWN BY: T. SMOCK ENGINEER: T. SMOCK
		Nov-20-15 Nov-20-15
		SCALE: 0.125 SHEET: 1 OF 1

REV A

Material Properties	
Grade	1005-1026
Shape	Square Tube
Wall Thickness	0.120" ± 0.012"
Straightness Tolerance	1/16" per 3'
Yield Strength	32,000 psi
Specification Met	ASTM A513
Construction	Hot Rolled
Material Composition	-
Carbon	0.13-0.20%
Manganese	0.30-0.90%
Silicon	0.15-0.30%
Phosphorous	0.04% Max
Sulfur	0.50% Max
Iron	98.06-99.42%
Nominal Density	0.283 lb/cu. in.
Thermal Coefficient of Expansion per °F	6.7-7.5e-6
Elongation Range	10-36%

Attachment #2 Seismic Bracket Kit

REAR_ANGLED_TAB_TOP Welded to REAR_ANGLED_SQUARE_TUBE

Fastened to REAR_LEFT_VERT_SQUARE_TUBE w/ 3/8" Bolt

REAR_ANGLED_TAB_BOT Welded to REAR_ANGLED_SQUARE_TUBE


Fastened to REAR_RIGHT_VERT_SQUARE_TUBE w/ 3/8" Bolt

D

C

B

A



REV	DESCRIPTION	BY	PCN	DATE	ENG
-	INITIAL RELEASE	-	-	Nov-20-15	-

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.
TOLERANCES AS FOLLOWS:
DECIMALS - ± .031
ANGLES - ± 1°

FINISH: ROUGH

MATERIAL:
LOW-CARBON STEEL

CLIMA COOL
ULTIMATE CLIMATE SOLUTIONS

15 S. Virginia Avenue
Oklahoma City, Ok 73106
Ph: 405-815-3000
Fax: 405-815-3052

TITLE: **STEEL, SQUARE TUBE**

Pro/E	DRAWING NO:	REAR_ANGLED_WELDED_TABS	
SIZE	DRAWN BY: T. SMOCK	Nov-20-15	SCALE: 0.125
A	ENGINEER: T. SMOCK	Nov-20-15	SHEET: 1 OF 1

REV A

DESCRIPTION	QTY.	
RAW STEEL (10 GA.)	Net Qty.	
	3.994 Lbs.	
PAINT	Paint Qty.	Surf. Area
	0.041 Lbs.	1.495 in^2

NOTE:
MATERIAL TO BE G60 GALVANIZED STEEL
UNLESS OTHERWISE NOTED

Attachment #2 Seismic Bracket Kit

Fastened to
TOP_HORIZNTL_LEFT_SQUARE_TUBE w/ 3/8" Bolt

2.000


1.500

29.045

114.0°

Fastened to Header Support Bracket
w/ 3/8" Bolt

115.1°



REV	DESCRIPTION	BY	PCN	DATE	ENG
-	INITIAL RELEASE	-	-	Nov-20-15	-

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.
TOLERANCES AS FOLLOWS:
DECIMALS - ± .031
ANGLES - ± 1°



15 S. Virginia Avenue
Oklahoma City, Ok 73106
Ph: 405-815-3000
Fax: 405-815-3052

TITLE: UPPER FRONT ANGLED BRACE


Pro/E DRAWING NO: UPPER_FRONT_ANGLED_BRACE

SIZE A	DRAWN BY: T. SMOCK ENGINEER: T. SMOCK	Nov-20-15 Nov-20-15	SCALE: 0.175 SHEET: 1 OF 1	REV A
-----------	--	------------------------	-------------------------------	----------

DESCRIPTION	QTY.	
RAW STEEL (10 GA.)	Net Qty.	
	3.994 Lbs.	
PAINT	Paint Qty.	Surf. Area
	0.041 Lbs.	1.495 in^2


NOTE:
MATERIAL TO BE G60 GALVANIZED STEEL
UNLESS OTHERWISE NOTED

Attachment #2 Seismic Bracket Kit



Fastened to
TOP_HORIZNTL_RIGHT_SQUARE_TUBE w/ 3/8" Bolt

Fastened to Left Header Support Bracket
w/ 3/8" Bolt



REV	DESCRIPTION	BY	PCN	DATE	ENG
-	INITIAL RELEASE	-	-	Nov-20-15	-

UNLESS OTHERWISE SPECIFIED
DIMENSIONS ARE IN INCHES.
TOLERANCES AS FOLLOWS:
DECIMALS - ± .031
ANGLES - ± 1°

FINISH: SEE CHART

MATERIAL:
10 GA.

		15 S. Virginia Avenue Oklahoma City, Ok 73106 Ph: 405-815-3000 Fax: 405-815-3052	
TITLE: UPPER FRONT ANGLED BRACE			
Pro/E	DRAWING NO: UPPER_REAR_ANGLED_BRACE		
SIZE A	DRAWN BY: T. SMOCK	Nov-20-15	SCALE: 0.175
	ENGINEER: T. SMOCK	Nov-20-15	SHEET: 1 OF 1
			REV A